

## SPESIFIKASI

### KERJA – KERJA MEMASANG SERTA MENGUJILARI 1 UNIT COLD – ROOM BERUKURAN P10KA X L8KA X T8KA. LENGKAP DENGAN SISTEM PENYEJUKAN, 1 UNIT GEN – SET SERTA KERJA ELEKTRIKAL BERKAITAN

- a. Description: injection pre – fabricated polyurethane panel for wall and ceiling, PU slab for floor insulation
- b. Dimension : 10'x8'x8'
- c. Thickness of panel : 75mm
- d. Density : 42 kg/m<sup>3</sup>,
- e. Facing material : 0.45mm colorbond
- f. Joining : Semi – camlock system, aluminium angel and non setting sealant
- g. Door : 1 unit swing door c/w 1 set pvc strip and internal safety release handle
- h. Floor : 1 layer 75mm thick c/w vapour seal
- i. standby power unit : 1 unit generator set (diesel ) c/w panel board (auto back - up)
- j. Cooling system : 1 unit outdoor compressor, indoor blower unit and panel board
- k. Warranty : 6 month